ADD CONTROLTECH SDN.BHD.(1001302-D)
NO:29-1,Jalan RS 1,Rawang Sentral,
48000 Rawang Selangor Darul Ehsan ,Malaysia.
Tel / Fax : 603-6093 6950
Specialized in : Automation Control System , PLC Programming ,AC & DC Drive Commissioning,Power Quality Inspection.

Date: 23 Aug 2018

QUOTATION

Our Ref: Q18-1421-LPH

Leopad Holdings Sdn.Bhd.
Wisma Leopad,2nd Floor,
No: 5,Jalan Tun Sambanthan,
50470 Kuala Lumpur, Malaysia.

Attn: Mr. Ruben.

RE: QUOTATION

We thank you for your inquiry and have pleasure to forward herewith our quotation for your consideration:

No	Item	Units	Qty	U/Price (RM)	Total Price (RM)
	Work Site: Ray Parc Hotel,Seputeh. **To refurbish the roof top booster pump system.**				
1.00	To supply and install inverter for booster pumps,1.5Kw,415vac,50Hz. Inverter maker option LS/Fuji/Siemen Micro Master. Work come with item: To remove old faulty inverters and rewiring the inverter panel. To set inverter parameter to booster pump operation.	lot	2	RM3,550.00	RM7,100.00
2.00	To supply and install differential pressure switches. Perform working pressure while testing the system.	lot	2	RM650.00	RM1,300.00
3.00	To refurbish the old control panel to new wiring system for the booster pumps to be control in Auto/Semi-Auto/Manual.	lot	1	RM3,300.00	RM3,300.00
3.10	To supply all relevent such,selector sw,relay,latching relay,timer,pilot lamps.				
3.20	To extent secondary pump wiring with junction box installation.				
3.20	To relocate old panel below the shed area.				
3.30	To provide electrical drawing for booster pump system.				
4.00	To suppy and install booster pump at roof top,multistage pump,12 m3/hr,H14 meter.Electrical specs,1.1Kw/415vac/50Hz.Maker Groundfos(china) /Teral(Japan). Installation c/w fitting,rubber gasket,alingment rubber pad and pump metal housing.	lot	2	RM3,600.00	RM7,200.00
4.00	Testing and commissioning.	lot	1	RM600.00	$600.00
5.00	After installation service for twice at site.	lot	1	RM0.00	RM0.00
			Grand Total		**RM19,500.00**

Term and Condition
Validity: 30 days from date of quotation.

Note:
Price above is including labours and transportation chargers.

Payment Term: Work will commence upon receiving Purchase order and 50% deposite
Balance 50% payment upon job completion-30 days
Late payment after the 30 days terms ,will charge interest 1.5% per month.

Delivery : 2-3 weeks upon receiving deposite and purchase order.

We trust , you will find our quotation favorable and look forward to receiving your valuable order soon.

Your faithfully,

Kumar
Technical Manager on behalf ADD Controltech SB
HP: 016-9933950

Received and Agreed

Person Incharge Signature
Company Stamp:
Date: